

# Value Management Recommendations

October 25, 2005



- Methodology
- Detector Enclosure Roof
- Single Aisle Access
- Overburden Depth
- Lift-A-Loft vs. Catwalks



# Methodology

 Done in compliance with DOE's Value Management principals.

The Value Method (VM) is a systematic and organized way to develop and compare alternatives that will get the job done (provide all of the essential functions) with the greatest value (greatest efficiency, economy, and quality with the least delay). The Value Method produces recommendations, not decisions.

http://oecm.energy.gov/Default.aspx?tabid=77



#### OECM Home OECM News Project Management

- Policies & Directives
- Guidance
- Studies & Reports
- Secretary of Energy's Project Management Excellence Awards Program

#### Communities of Practice

- Earned Value Management
- Value Management
   Regulations, Policy
- Requirements
   Resources
- Message Bo
- Message Br
- LIIK

#### nterest Areas

- cost Engineering sject Assessment and seporting System
- Project Management Career Development Program
- Acquisition Strategy
   Real Property Asset Management Plan

#### acilities & Infrastructure

- Policies & Directives
- Folicies & Directives
   Guidance
- Broadband Deployment

#### Value Management

#### Welcome

Welcome to the U.S. Department of Energy's Value Management Information Center (VMIC). The VMIC has been created to assist the Department's value and project management communities in sharing relevant information, discussing issues, learning more about the value methodology, and providing a forum to share lessons-learned across the DOE community.

The Value Method (VM) is a systematic and organized way to develop and compare alternatives that will get the job done (provide all of the essential functions) with the greatest value (greatest efficiency, economy, and quality with the least delay). The Value Method produces recommendations, not decisions. The Value Method includes the processes known as Value Analysis, Value Engineering, and Value Management. It is sometimes also referred to as Value Control, Value Improvement or Value Assurance.

The VMIC is sponsored by the Office of Engineering and Construction Management.

#### Announcements

#### Value Engineering Policy

To establish Department of Energy (DOE) value engineering policy that meets the requirements of Public Law 104-106, Section 4306 as codified by 41 United States Code 432. This law states that each agency shall establish and maintain cost-effective value engineering (VE) procedures and processes. Additionally, Office of Management and Budget (OMB) Circular A-131, Value Engineering, requires that all Federal agencies use VE as a management tool, where appropriate and using a graded approach, to ensure realistic budgets, identify and remove nonessential capital and operating costs, and improve and maintain optimum quality of program and acquisition functions. read more...

Additionally, Office of Management and Budget (OMB) Circular A-131, Value Engineering, requires that all Federal agencies use VE as a management tool, where appropriate and using a graded approach, to ensure realistic budgets, identify and remove nonessential capital and operating costs, and improve and maintain optimum quality of program and acquisition functions.




#### THE VALUE METHODOLOGY JOB PLAN

The Value Methodology uses a systematic Job Plan. The Job Plan outlines specific steps to effectively analyze a product or service in order to develop the maximum number of alternatives to achieve the product's or service's required functions. Adherence to the Job Plan will better assure maximum benefits while offering greater flexibility.





- Utilized STAAD
   Structural Analysis
   Program
- Modeled and Run by Russ Alber (FESS/E)






- Base Scheme 77'-0" Span
  - 55' Detector Envelope

modules+manifolds+cable tray + piping

### - 11' Aisles

- 7'-0" for Lift-A-Loft + 4'-0" for exiting
- 10' of overburden
- Steel Truss System
  - Allows Top Access
  - Fabricated Off Site
  - Conducive to Winter Conditions






- Option 1 65'-0" Span
  - 55' Detector Envelope
  - 5' Aisles

 Catwalks in lieu of Lift-A-Loft


– 10' of overburden

Steel Truss System





- Option 2 55'-0" Span
  - 55' Detector Envelope
  - 6' Aisles
    - Catwalks
  - 10' of overburden
  - Steel Truss System
    - Columns adjacent to Detector
    - Columns also support the catwalks





- Evaluation Included
  - Cost
  - Compatibility with other systems
  - Constructability
  - Life Cycle Concerns




### **Selected Cost Drivers**

Scheme Designation		Base	65' Span	55' Span	
Structural Steel	K/Bent		68	55	30
	Total Steel (tons)		1615	1306	713
Excavation	Width		77	65	67
	Total Excavation (cu-yds)		64167	54167	55833
Base Slab	Total Conc. (cu-yds)		1925	1625	1675
Berm	Total Backfill	(cu-yds)	2822	2556	2600
Retaining Wall	Total Conc.	(cu-yds)	6000	6000	3000



### **Comparative Cost Summary**





## Single Aisle Access

- Base Scheme 77'-0" Span
  - 55' Detector Envelope

modules+manifolds+cable tray +


piping

– 11' Aisles

• 7'-0" for Lift-A-Loft + 4'-0" for exiting

– 10' of overburden

Steel Truss System





## Single Aisle Access


- Option 55'-0" Span
  - 56' Detector Envelope

- 6' Aisle

• Catwalks in lieu of Lift-A-Loft

- 10' of overburden

- Steel Truss System
- Columns to SupportCatwalk



62'-0"




### **Selected Cost Drivers**

Scheme Designation		Base	1-Aisle	
Structural Steel	K/Bent		68	29
	Total Steel (tons)		1615	689
Excavation		Width	77	62
	Total Excavation	(cu-yds)	64167	51667
Base Slab	Total Conc. (cu-yds)		1925	1550
		, ,	2222	0.100
Berm	Total Backfill	(cu-yds)	2822	2489
Data'a'a a Mall	Tallal	/	0000	0000
Retaining Wall	Total Conc.	(cu-yas)	6000	3000



### **Comparative Cost Summary**






- Base Scheme 10' Depth
- Significant Cost Drivers
  - Same as Other VM recommendations
  - Structural Steel
  - Excavation
  - Concrete Base Slab
  - Overburden
  - Concrete Retaining Wall
- Included All Spans + Single Aisle Scheme




### **Comparative Cost Summary**





- Lift-A-Loft proposal
  - Model LAL 65.0
  - 65' platform height
  - 7' wide x 13'
  - \$184,052 each x 2 = \$368k
- Catwalks
  - Utilizes steel columns from 55' span option
  - Includes






### Lift-A-Loft vs. Catwalk

### Catwalks

- Utilizes steel columns from 55' span option
- Provides 44" clear aisleway
- Steel grating





• Formalize these recommendations per the DOE guidelines